REQUEST FOR PROPOSAL

Main Switchboard and Power Management System

Project	OSV-45 Multipurpose Offshore Support Vessel (Hull 101)
Document No.	EX-101-RFP-052
Revision	0
Date	10.04.2026
Prepared by	Example Shipbuilders Ltd.
Bid due date	15.05.2026
Bid validity	90 days from bid due date

1. Instructions to Bidders

1.1 Example Shipbuilders Ltd. invites offers for the supply of a main switchboard and power management system (PMS) for Hull 101.

1.2 Bids shall remain valid for 120 days from the date of opening.

1.3 Technical and price bids shall be submitted in separate envelopes. Queries shall be submitted in writing before the pre-bid meeting.

1.4 Delivery shall be as early as possible and in line with the shipbuilding schedule.

2. Technical Scope

2.1 The switchboard shall be suitable for the generators and loads of the vessel, in two sections with a bus-tie.

2.2 Rated voltage shall be 415 V AC, 3-phase, 50 Hz. The busbar short-circuit withstand rating shall be suitable for the fault level of the system.

2.3 Degree of protection shall be IP22 for the switchboard enclosure. The enclosure shall also meet IP44 where installed in machinery spaces.

2.4 Breakers shall be of a reputed make. Generator breakers shall be withdrawable; feeder breakers shall be as per vendor standard.

2.5 The PMS shall provide automatic start, synchronising, load sharing, load-dependent start and stop, and preferential tripping.

2.6 The PMS shall interface with the ship's alarm and monitoring system. Details of the interface will be provided later.

2.7 The equipment shall comply with the relevant standards and classification society requirements.

3. Testing and Documentation

3.1 Factory acceptance tests shall be carried out as necessary. Class witness charges shall be borne by the party as mutually agreed.

3.2 The vendor shall submit standard documents with the bid and all other documents after the order.

4. Commercial Conditions

4.1 Standard spares shall be included in the scope of supply.

4.2 Warranty shall be as per the shipbuilding contract.

4.3 Liquidated damages shall apply for delay in delivery. The rate and ceiling are as per company policy.

4.4 Payment terms shall be discussed during negotiation.